



KEY FEATURES

- Construction in the middle of the City's downtown business district on Route 14/302.
- Nighttime construction to minimize impacts to Main Street businesses.
- Replacement of 2,500' of 30" sewer and 700' of 24" sewer, known locally as the Westside Trunkline.
- Replacement of 2,600' of 16" water main with services and fire protection sprinkler lines to all commercial buildings.
- All roof drains separated from the sewer collection system.
- Abandonment of existing water and sewer main in the street with flowable fill.
- Construction observation and record drawing preparation for underground electric conduits installed in anticipation of the project.

The VTrans funded City of Barre North Main Street project has been planned for decades, but was delayed until 2011 due to the major challenges to construction associated with reconstructing roadways and utilities on a state highway in the middle of the City.

Dufresne Group provided design and construction phase services for replacement of the underground utilities. On site Resident Project Representation included nighttime work as the contractor operated multiple crews to minimize traffic disruptions and impacts to businesses.