



***Leigh LaRock of Construction Materials Testing, Inc. Checks Compaction***



***Heath Construction Begins Work in Early October***

System water pressure was virtually non-existent during the day for the 38 users on the Lyn Haven Water system. The 30 year old 1-inch diameter distribution system was nearly plugged with calcium carbonate allowing only a small trickle to reach the customers.

Dufresne Group worked with Duane Gilman, a Fire District volunteer, to define a complete replacement project for about \$1.00 per day per user. Construction began in October and water service was initiated in December 2001.

### KEY FEATURES

- 75% RD Grant
- \$1.00 Per Day Per User
- Evaluation Report performed by State at no cost
- Two cell concrete water storage tanks
- Radio telemetry system
- Water softener
- Chlorine contact time compliance
- Income survey by Rural Water